

SITE VISIT ESTIMATE

CUSTOMER	Muru
PHONE	60167206755
GROUP	SE-0526-001 Muru
ADDRESS	Jalan Indah 24/6
PROBLEM	
INSPECTED BY	Osment (JB)

Slab 1

SLAB + UPTURNS



MEASUREMENTS

Floor area

582.6 sqft

UPTURNS

L	63 ft	× 1.5 ft	= 94.5 sqft
R	61 ft	× 1 ft	= 61.0 sqft
M	6 ft	× 2 ft	= 12.0 sqft
Total upturn			167.5 sqft

Total membrane area

750.1 sqft

Membrane installation @ RM 8.50/sqft

RM 6,376.11

ADDITIONAL SERVICES

Water tank removal	1 job	@ RM 650.00	RM 650.00
Existing coating removal	750 sqft	@ RM 0.50	RM 375.00
Services subtotal			RM 1,025.00

Slab 1 subtotal

RM 7,401.11

Slab 2		FLASHING / LINEAR	
			



MEASUREMENTS

LINEAR SECTIONS			
L	40 ft	× 0.5 ft	= 20.0 sqft
R	40 ft	× 3 ft	= 120.0 sqft
Total upturn			140.0 sqft
Total membrane area			140.0 sqft
Membrane installation @ RM 8.50/sqft			RM 1,190.00
Slab 2 subtotal			RM 1,190.00

Additional Costs (site-wide)

Scaffolding supply & deliver	1 job	@ RM 800.00	RM 800.00
Additional Costs subtotal			RM 800.00

ESTIMATED TOTAL — BREAKDOWN

Slab 1

Membrane (750.1 sqft × RM 8.50)	RM 6,376.11
Water tank removal	RM 650.00
Existing coating removal	RM 375.00

Subtotal	RM 7,401.11
----------	-------------

Slab 2

Membrane (140.0 sqft × RM 8.50)	RM 1,190.00
---------------------------------	-------------

Subtotal	RM 1,190.00
----------	-------------

Additional Costs (site-wide)

Scaffolding supply & deliver	RM 800.00
------------------------------	-----------

Subtotal	RM 800.00
----------	-----------

TOTAL	RM 9,391.11
-------	-------------

TERMS & CONDITIONS

- This estimate is valid for **14 days** from date of issue.
- A final formal quotation will be issued upon project confirmation.
- Estimate is subject to actual site conditions on installation day; minor adjustments may apply.
- Waterproofing membrane carries a **5-year workmanship warranty** from project completion.

- Waterproofing membrane comes with 5 year workmanship warranty from project completion.
- All payments must be made via official Innovation AID Sdn Bhd channels only.
- Customer to ensure site access on the agreed installation date.

INSPECTED BY

ACKNOWLEDGED BY

Osment (JB)
Date: 26 May 2026

Muru
Date: _____